

Tab. 3.3 - Tabela robót ziemnych

BILANS ROBÓT ZIEMNYCH							
Pikieta	Pow. wykopu	Pow. nasypu	Obj. wykopu	Obj. nasypu	Całk. obj. wykopu	Całk. obj. nasypu	Obj. netto
1+926.8	0.4	3.0	19.4	79.87	1606.40	3550.54	-1944.15
1+942.6	0.7	1.5	8.8	35.69	1615.23	3586.24	-1971.01
1+958.6	0.6	0.9	10.1	18.69	1625.34	3604.93	-1979.59
1+985.3	1.4	0.7	26.3	20.59	1651.66	3625.52	-1973.86
2+016.4	0.6	1.1	31.3	28.30	1682.94	3653.82	-1970.88
2+029.7	1.0	0.8	10.9	12.64	1693.85	3666.46	-1972.61
2+030.3	1.1	0.7	0.6	0.44	1694.49	3666.90	-1972.41
2+046.8	3.1	0.0	34.4	5.84	1728.91	3672.74	-1943.82
2+079.4	4.0	0.1	115.6	1.99	1844.56	3674.72	-1830.17
2+113.5	7.5	0.0	195.2	2.31	2039.78	3677.04	-1637.26
2+124.7	8.3	0.0	88.6	0.24	2128.39	3677.28	-1548.89

OD CAŁKOWITEJ ILOŚĆ NASYPÓW NALEŻY ODJAĆ ILOŚĆ  
KRUSZYWA POTRZEBNEGO DO WYRÓWNANIA  
POD PROJEKTOWANĄ NAKŁADKĘ (TAB. NR 3)

CAŁKOWITA OBJĘTOŚĆ NASYPU =3677,28-1459,20=2218,08