

Tab. 2 - Tabela robót ziemnych

BILANS ROBÓT ZIEMNYCH - ul. Sobieskiego							
Pikieta	Pow. wykopu	Pow. nasypu	Obj. wykopu	Obj. nasypu	Catk. obj. wykopu	Catk. obj. nasypu	Obj. netto
0+045.4	0.0	0.0	0.0	0.00	0.00	0.00	0.00
0+058.6	4.7	0.0	31.2	0.00	31.24	0.00	31.24
0+064.0	4.7	0.0	25.5	0.00	56.69	0.00	56.69
0+089.0	5.0	0.0	121.9	0.00	178.64	0.01	178.63
0+115.3	4.4	0.0	124.6	0.00	303.24	0.01	303.23
0+131.4	4.1	0.0	68.7	0.11	371.92	0.12	371.80
0+131.8	4.1	0.0	1.8	0.01	373.70	0.13	373.57
0+139.4	4.1	0.0	31.3	0.11	405.04	0.24	404.80
0+164.7	4.2	0.0	105.2	0.33	510.26	0.57	509.69
0+180.1	4.4	0.0	66.4	0.09	576.65	0.66	576.00
0+184.2	5.5	0.0	20.3	0.05	596.95	0.70	596.25
0+190.1	5.3	0.0	31.7	0.18	628.67	0.88	627.79
0+215.9	6.9	0.0	158.2	0.52	786.89	1.41	785.49
0+238.5	6.4	0.0	150.3	0.11	937.16	1.52	935.64
0+250.3	6.3	0.0	74.2	0.17	1011.34	1.68	1009.66
0+253.6	5.6	0.0	19.8	0.07	1031.17	1.76	1029.41
0+260.4	5.3	0.0	37.0	0.25	1068.12	2.01	1066.12
0+282.9	6.4	0.1	131.1	1.30	1199.20	3.31	1195.89
0+283.3	6.4	0.0	2.6	0.02	1201.75	3.33	1198.43
0+291.7	5.9	0.0	51.1	0.13	1252.86	3.45	1249.41
0+307.1	3.7	0.4	73.9	3.48	1326.78	6.93	1319.84
0+313.7	3.7	0.7	24.2	3.69	1351.00	10.62	1340.37
0+315.7	5.6	0.1	9.3	0.75	1360.30	11.37	1348.93
0+316.6	5.6	0.1	4.6	0.06	1364.93	11.43	1353.50
0+331.7	6.4	0.0	91.1	0.65	1456.08	12.08	1443.99
0+355.2	6.7	0.0	154.4	0.67	1610.45	12.76	1597.69
0+374.0	6.3	0.1	122.7	1.20	1733.16	13.96	1719.20
0+387.1	5.9	0.2	79.5	1.55	1812.66	15.51	1797.15
0+398.9	5.3	0.2	66.2	2.02	1878.86	17.54	1861.32
0+400.9	4.9	0.2	10.3	0.38	1889.18	17.92	1871.26
0+414.0	5.2	0.3	65.7	3.03	1954.87	20.95	1933.92
0+430.2	5.5	0.2	86.5	4.05	2041.40	25.01	2016.40
0+445.7	4.6	0.1	78.9	2.86	2120.27	27.87	2092.40
0+455.3	5.1	0.2	46.4	1.46	2166.67	29.33	2137.34
0+468.7	5.2	0.1	68.8	1.77	2235.48	31.10	2204.38
0+482.1	4.5	0.2	64.7	1.88	2300.15	32.98	2267.17
0+517.4	4.4	0.1	156.0	4.81	2456.17	37.79	2418.38
0+527.9	5.4	0.1	51.6	0.82	2507.76	38.61	2469.15
0+538.0	6.3	0.0	59.0	0.47	2566.77	39.08	2527.69
0+539.4	3.6	0.1	6.1	0.10	2572.88	39.18	2533.71
0+545.3	3.6	0.1	21.0	0.67	2593.91	39.84	2554.07
0+549.9	3.5	0.1	16.3	0.45	2610.22	40.30	2569.92
0+552.8	1.2	0.2	6.9	0.44	2617.13	40.73	2576.40
0+559.5	1.3	0.2	8.1	1.36	2625.27	42.09	2583.18